



West Valley Demonstration Project

Project Overview

October 25, 2006

18890_1






WVDP Background

1962 Nuclear Fuel Services reached an agreement with the Atomic Energy Commission and New York State to construct the first commercial nuclear fuel reprocessing plant in the United States

1962 - 1966 — Reprocessing Plant Constructed



1966 - 1972 Spent nuclear fuel was reprocessed; majority supplied by federal government —600,000 gallons of liquid high-level waste resulted

1972 - 1976 The reprocessing plant was shut down for modifications; operations were never resumed




1982—Reprocessing Plant

18890_3




Reprocessing




Nuclear fuel assemblies typically 7 feet to 14 feet long

Chop and Dissolve in Acid



Liquid High-level Waste



Usable uranium and plutonium

18890_4



High-level Waste (HLW) Tank

HLW Tank Cross Section




Circular tank about 70' in diameter, 27' high

18890_5



West Valley Demonstration Project






WVDP Background — The Act

- ◆ October 1, 1980
 - Public Law 96-368 signed into law by President Carter in Niagara Falls, NY
 - Act authorizes the U.S. Department of Energy to conduct a high-level radioactive waste management demonstration project at the Western New York Nuclear Service Center (the Center)



Pretreatment/Sludge Washing Operations

- ◆ Four-part Integrated Radwaste Treatment System
 - Separated out salts and sulfates
 - Blended in cement
 - Placed drums of cemented waste in storage
- ◆ 1988-1990 - removal of salts from liquid portion of waste in underground waste tank (8D-2)
- ◆ 1991 - 1995 - sludge washing operations to remove salts and sulfates
- ◆ Total operations processed 1.7 million gallons of low-level salt solution into 19,877 drums of cemented LLW currently stored in the Drum Cell



71-gallon drums of cemented waste in storage at the WYDP.

16890_9



Curies – Radionuclide – Half Life 1,000 curies

	Cobalt-60 (~5 yr.)	Cesium-137/ Strontium-90 (~30 yr.)	Americum-241 (~433 yr.)	Technicium-99 (~211,000 yr.)
Day 0	1,000	1,000	1,000	1,000
30 years	15	500	930	1,000
60 years	0.23	250	861	1,000

1 curie = 3.7×10^{10} disintegrations per minute

Note: Radionuclides don't all give off same type(s) of radiation

16890_10



Radioactive Decay

Example

Strontium-90
(~30 years)

Yttrium-90
(64 hours)

Zirconium
(stable)

18890_11



High-Level Waste (HLW) Vitrification Began with Process Design

To solidify the radioactive material from approximately 600,000 gallons of high-level radioactive waste into a durable, high-quality glass, both a pretreatment system to remove



High-level Waste Processing


- ◆ Vitrification program a significant technological and environmental success
 - Liquid waste threat eliminated
 - Vitrification system operated better than predicted
 - 78% availability the first year
 - No failures of major components

Vitrification Campaign Statistics	
Pretreatment	Vitrification
<ul style="list-style-type: none">• 1.7 million gallons processed• 19,877 drums of cemented low-level waste produced	<ul style="list-style-type: none">• More than 1.3 million pounds of waste glass produced• More than 24 million curies processed• Approximately 35% waste loading in glass• Canister dose rates range from ~2000 - 7000 R/hr on contact

18890_15



Major Site Facilities Today



Estimated Total Curies at the West Valley Demonstration Project
October 25, 2006



2002 – 2006 Work Focused on Completing WVDP Act Mandates

- ◆ **Dispose of Project generated low-level waste and Transuranic waste**
- ◆ **Decontaminate and decommission the tanks, facilities, and any material and hardware used in connection with the Project**
- ◆ **Transport HLW canisters to Federal Repository**
 - working
 - on hold

18890_17



WVDP National Environmental Policy Act Background

- | | |
|--------|---|
| 1982 | Environmental Impact Statement (EIS) and Record of Decision for HLW processing |
| 1986 | Environmental Assessment for on-site low-level waste disposal <ul style="list-style-type: none">— litigated— evaluation deferred to closure EIS |
| 1988 – | National effort to develop regional LLW sites |
| 1992 | (Intent was to dispose of all LLW on site; dispose of transuranic and HLW off site) |
| 1996 | Draft EIS for WVDP completion and long-term site management released for public review; for LLW considered on-site storage and disposal, and off-site disposal |
| 1997 | WVDP began disposition of LLW off site |
| 2001 | Rescoped EIS <ul style="list-style-type: none">— new EIS for off-site shipment of WVDP wastes for disposal— focused completion/closure EIS on facilities posing greatest long-term environmental risk; disposal areas, reprocessing plant, underground tanks |

18890_18



WVDP National Environmental Policy Act Background

- 2003 Notice of Intent to prepare Decommissioning and/or Long-Term Stewardship at the WVDP and Western New York Nuclear Service Center
Notice of Availability of the WVDP Draft Waste Management EIS
- 2004 Notice of Availability of the WVDP Final Waste Management EIS
- 2005 Record of Decision following WVDP Final Waste Management EIS


18890_19



Work Accomplished Between 2002 - 2006

- ◆ Completed construction and operated Remote-Handled Waste Facility
- ◆ Shipped remaining used nuclear fuel to DOE's Idaho facility for storage
- ◆ Shipped over 800,000 cubic feet of low-level waste for disposal
- ◆ Remotely dismantled, and removed and packaged vitrification processing equipment
- ◆ Drained and shut down the used fuel storage pool
- ◆ Removed and packaged contaminated hardware from highly radioactive chambers in the reprocessing plant
- ◆ Removed and demolished unneeded, excess facilities
- ◆ Dispositioned equipment in open storage areas (hardstands)

18890_20



Remote-Handled Waste Facility



Spent Fuel Shipment




LLW Shipment



Vitrification Facility Decontamination



Funding and Headcount



18890_23



WVDP 2007 - 2010

- ◆ DOE issued Request for Proposals for new primary contractor to begin January 1, 2007
- ◆ A WVDP Interim End State to be achieved by 2010
 - Description in DOE WVDP Site Utilization Management Plan August 2005

18890_24



Interim End State Completion - 2010

